

Addendum 3

1. Drawings are now available.
2. Bid opening / due date extended from 2pm Sept. 17th to 2:30pm Sept. 24th
 - a. Bids are due at 2pm in City Hall
 - b. Bids will be opened virtually at 2:30pm using this link
3. Questions due in writing by 11:59pm on Thursday, Sept 17th
 - a. City will address these questions in future addendums as needed
 - b. All questions will be answered by 5pm Monday, Sept 21st
4. City is adding curb replacement to the sidewalks between Beechurst and Grant.
 - a. Curb **quantities updated** from 1279 LF to 1652 LF
5. Standard sidewalk detail updated; please refer to plan general detail page for latest updated spec. Summary below:
 - a. Fiber reinforcement acceptable in lieu of WWF
 - b. Aggregate base options expanded
 - c. Standard widths table deleted, refer to bid quantities for the four distinct sections of the project which each receive their own width and/or other defining characteristics, such as the integral knee wall.
6. Contractor responsible for securing 3rd party, independent materials testing
 - a. Follow *Specifications for Structural Concrete*, **ACI 301-96**, or WVDOH equivalent.
 - i. Must obtain at least one composite sample for each 100 cubic yards, or fraction thereof, of each design mixture of concrete placed in any one day.
 - ii. Composite samples must be taken in accordance with *Standard Practice for Sampling Freshly Mixed Concrete*, ASTM C 172, or WVDOH equivalent.
 - iii. Strength and Air-content tests must be conducted on each sample.
 - iv. Slump tests are required for each composite sample and whenever consistency of the concrete appears to vary.
 - v. Air-content tests may be taken on composite samples or on samples from the batch taken at any time after discharge of 2 cubic feet of concrete.
7. Tree protection clause added
 - a. Wherever contractor falls under the canopy of a tree or encounters apparent tree roots, contractor must alert PM and take the following precautions:
 - i. Contractor must hand dig to expose roots
 - ii. Contractor must make a clean cut with sharp tools to prune roots flush to edge of excavation.
 - iii. Contractor must cover root after cutting with damp soil or other means to prevent root from drying out.
8. Utility notes:
 - a. City/Owner will coordinate all necessary utility relocations, including the guywire support on the combined power/communications pole just south of McClane Avenue.
 - b. The Dominion/Hope contractor notes that the top of the recently installed plastic gas line sits 30" below the surface of the concrete capped trench along Eighth Street.
 - i. There is a continuous ribbon 6" above the top of the gas line.
 - ii. There is an abandoned steel gas line behind the curb at an unknown depth.